



City of Elko Clerk's Department
1751 College Avenue
Elko, NV 89801
(775) 777-7126
FAX (775) 777-7129

ADDENDUM NUMBER ONE

WRF DIGESTER AND BOILER UPGRADE

Dated this 23 day of November, 2021

Please confirm receipt of ADDENDUM NUMBER ONE AND FAX BACK TO (775) 777-7129 or
email to cityclerk@elkocitynv.gov.

SIGNATURE

COMPANY NAME

DATE

Elko City Clerk
Kelly Wooldridge

***** PLEASE NOTE RECEIPT OF ADDENDUM NUMBER ONE ON
APPLICABLE LINE ON SUBMITTED BID PROPOSAL ***

Bid Addendum #1

PWP EL-2022-081

WRF Digester Maintenance and Boiler Upgrade Project

The following are clarifications or additional information for bidders and will be incorporated into the project contract with the successful bidder:

- 1) Bid Item No. 1-
 - a. Insulation on the digester tube assemblies to consist of 1.5-inch thick fiberglass pipe insulation with stucco embossed aluminum jacket material.
 - b. Existing pressure transducers and temperature gauges to be removed and reused on new digester tube installation.
 - c. The outside company performing the service work on the mixer assemblies will need 4 weeks advance notice to schedule the mixer service, and will need the mixers to be staged for the service work for a minimum of 10 days.
- 2) Bid Item No. 9
 - a. All piping inside the boiler room associated with the new boiler to be replaced with new. This includes pipework for natural gas, digester gas, hot water, and return water. All removed materials to be given to Owner for rebuild or recycle.
 - b. 2 of the existing water pumps in boiler room to remain in place, and remain in service. One of the pumps to be removed.
 - c. The existing pedestals for the existing boiler will likely need to be removed and new pedestals specific to the new boiler assembly will need to be poured. This is dependent on actual boiler supplied.
 - d. A new roof penetration for the boiler flue outlet will likely be required, depending on boiler supplied. If new penetration is required the existing flue outlets to be capped by the contractor. This is dependent on actual boiler supplied.