

Nonpareil WTP Improvements



City of Sutherlin, Douglas County, Oregon

Project 146.54

City Council Meeting

January 11, 2021



The Dyer Partnership Engineers and Planners

Background

- Water Treatment Plant (WTP) Constructed in 1982
- City of Sutherlin's Primary WTP
- Design WTP Capacity (with Backwash) of 2.3 MGD
- Raw Water Pump Station and WTP Components
 - Raw Water Intake (Calapooya Creek) and Pump Station
 - Clarifier
 - Filters (Multimedia) with Backwash System
 - Clearwell and Treated Water Pumps
 - Sodium Hypochlorite Disinfection System
 - Chemical Feed Systems
 - Instrumentation Systems
 - Electrical Systems
 - Standby Generator
 - Backwash Ponds



WTP Deficiencies

- Raw Water Pumps and Control Panel / Intake Systems
 - Beyond service life
 - No Variable Frequency Drives (VFDs)
 - Inadequately sized compressor
- Raw Water Flow Meter and Static Mixer
 - Beyond service life
- Clarifier
 - Concrete structure not watertight
 - Coating deficiencies
 - Tube settlers beyond service life
 - Maintenance accessibility limitations



WTP Deficiencies

- Multimedia Filters
 - Antiquated piping and actuated valves
 - Inefficient backwash system
 - Backwash pump beyond service life and doesn't include VFD or flow meter
 - No filter-to-waste piping and actuated valves
 - Aluminum filter tank deficiencies
 - Obsolete instrumentation systems
 - Media at end of service life
- Treated Water Pumps
 - Beyond service life
 - No VFDs (cannot sequence with Raw Water Pump Station)



WTP Deficiencies

- Clearwell
 - Coating deficiencies
 - Obsolete liquid level sensor
- Backwash Basins
 - Maintenance intensive sludge removal process
- Chemical Feed Systems
 - Beyond service life
 - Not integrated into plant control system
 - No redundancy
- Potable Water System
 - Beyond service life
 - Labor intensive removal and replacement process (confined space entry requirements)



WTP Deficiencies

- Instrumentation Systems
 - Beyond service life
 - Obsolete technology
 - Not completely integrated into plant control system
- Controls and SCADA
 - Beyond service life
 - Outdated technology
- Standby / Emergency Generator
 - Beyond service life
 - Reliability concerns



WTP Improvements Scope

- Intake Improvements
- Raw Water Pump Station Improvements
- Raw Water Flow Meter and Static Mixer Improvements
- Clarifier Improvements
- Filter Improvements
- New Filter Piping and Electronic Actuated Valves
- New Air Scour System
- New Backwash Pump
- New Treated Water Pumps
- New Backwash Basins
- New Chemical Feed Systems
- New Streaming Current Monitor



WTP Improvements Scope

- New Potable Water Pump System
- New Fencing and Gate
- New Yard Piping
- Electrical Improvements
- New Electrical Room and Blower Canopy
- New Standby Generator
- New Radio Telemetry System
- New Motor Control Center (MCC)
- New Plant-Wide WTP Control Panel
- New SCADA System




Raw Water Pump Station and Intake Improvements

- New Intake Compressor and Actuated Valve
- Raw Water Pump Station
 - New pumps and control panel
 - New piping and valves
 - New canopy
 - New radio telemetry system
 - New pressure transmitter
 - Electrical improvements
 - New fence and gate



Clarifier Improvements

- Clarifier
 - New tube settlers
 - Access walkway extension
 - Metal repairs
 - Lead paint removal and disposal
 - New coatings
 - Concrete tank pressure grouting
 - Launder improvements
 - New clarifier wasting valve (actuated) and flow meter



Raw Water Vault Improvements

- New Flow Meter
- New Static Mixer
- New Spare Chemical Feed Lines



Filter Improvements

- Filter Improvements
 - Aluminum filter tank repairs (outlets)
 - New underdrains
 - New media
 - New piping and appurtenances
 - New electronically actuated valves
 - New filter-to-waste piping and valves
 - New ultra-sonic level transducers
 - New air scour system (1 duty, 1 standby blower)
 - New backwash pump with VFD, pressure transmitter and flow meter
 - Demolition of existing surface wash system
 - Demolition of existing piping includes lead paint removal and disposal



Treated Water Pumps and Clearwell Improvements

- Treated Water Pumps and Clearwell
 - New treated water pumps (2 duty, 1 standby) with VFDs and pressure transmitter
 - New liquid level transducers (includes redundant unit)
 - New piping and valves
 - New treated water flow meter and access hatch
 - New coatings
 - New clear well piping
 - New clear well ladder



Potable Water Pump Improvements

- New Potable Water Pump
 - New pump
 - New redundant pump
 - New piping and valves
 - New backflow preventor
- New Pressure Tank
 - New pressure tank
 - New pressure switch
 - New piping and valves



Chemical Feed and Instrumentation Improvements

- Chemical Feed Systems
 - New duplex primary coagulant pump system
 - New duplex filter aid pump system
 - Integrated into plant wide control panel
 - New piping and appurtenances
 - Electrical improvements
- New Turbidimeters
 - Sample pumps and solenoid valves
 - Filter No. 1 – Filter No. 4 analyzers
 - Combined analyzer
- New Streaming Current Monitor



Backwash Basin Improvements

- New Backwash Basins
 - Two 150,000 gal basins
 - Concrete structure with handrails
 - Decant piping
 - Effluent piping and manholes



Controls, SCADA and Standby Power Improvements

- New Standby Generator
 - New 275 kW emergency generator
 - New automatic transfer switch
- New Electrical Room
 - New electrical room and canopy for air scour blowers
 - New MCC and plant-wide WTP control panel with touch screen HMI
 - New SCADA system
 - New desktop computer with cellular tablets
 - New reservoir telemetry control panel
 - New radio telemetry system for Raw Water Pump Station integration



WTP Site Improvements

- New Fencing and Gate
- New Yard Piping
- New Sidewalk
- New Gravel Surfacing



Construction Cost Estimate

- Volatile Market Conditions
 - Supply chain disruptions driving cost increases for materials (lumber, PVC, steel)
- Construction Cost Estimate
 - \$3,200,000 to \$3,900,000



Schedule

- Oregon Health Authority (OHA) Approval
 - December 2020
- Bid Process
 - January / February 2021
- Construction Schedule
 - Notice to proceed ~ March 2021
 - 18 month construction period
- WTP Shut-Down Periods
 - April 1, 2021 to June 30, 2021
 - March 1, 2022 to June 30, 2022
- Commission WTP by June 30, 2022



Questions and Comments

