

ITB 2022-11 HUDSON PARK IMPROVEMENTS
Addendum No. 1



Addendum No. 1 to ITB 2022-11

HUDSON PARK IMPROVEMENTS

June 17, 2022

SECTION 1.0 SCHEDULE OF EVENTS – Please see dates adjusted in RED below

Failure to comply with this or any other paragraph of this RFP shall be sufficient reason for rejection of the proposal.

All times listed in the Schedule of Events are Eastern Standard Time (EST).

<i>Event</i>	<i>Date/Time</i>
Bid Advertisement Date	May 26, 2022
Release of Invitation to Bid	May 26, 2022
Pre-Bid Conference	June 6, 2022 @ 10:00 A.M.
Bid Questions Due from Prospective Bidder	June 10, 2022
Responses to bid questions due	June 17, 2022
BIDS DUE TO BOCC	June 23, 2022 @ 3:00 P.M.
Posting of Intended Award	June 28, 2022
Board Consideration of Intended Award	July 18, 2022
Posting of Notice of Award	July 19, 2022

This addendum is being posted to provide answers to questions received.

ITB 2022-11 Hudson Park Improvements

Questions due June 10th and responses to bid questions due June 17th

Questions and Answers

Q1: What is the budget for this project?

A1: the total budget amount is \$152,398.00

Q2: What is length of construction time?

A2: The Work shall be substantially completed within 150 calendar days from the Commencement Date and fully completed by 180 days from the Commencement Date.

Q3: Are the bench specifications noted in the plans?

A3: Yes. Hudson Park + Sheet A0.2 Detail 3

Q4: What is the asphalt and base material thickness?

A4: Base is Lime Rock LBR 100, Detail, detail 5/A0.2, Contractor may combine 4" lime rock base with milled Asphalt to achieve specifications.

Asphalt is 1.5 Inches of 9.5 Asphaltic Concrete over a prime/tack coat. As defined in Section 334, FDOT. For specifications, please contact Michelle Metcalf at mmetcalf@mywakulla.com.

Q5: What depth is the conduit?

A5: 6" conduit at 24" depth to top of conduit, Detail 3/A0.3, with trace wires for locating